

Bill of Materials - RCP # 08-289

Wood							
Qty	Item	Pg	MK	Size	Length	Stress	Remarks
8 Pcs.	Column	5	C-1	5" x 8 1/4"	12'-0"	24F-V5	Glu-Lam, CCA 0.6 pcf
4 Pcs.	Column	5	C-2	5" x 5 1/2"	8'-0"	47(1:8)	Glu-Lam, CCA 0.6 pcf
11 Pcs.	Curved Beam	5	CB-1	5" x varies	50'-0"	24F-V3	Glu-Lam, Stained "Natural"
4 Pcs.	Rafter	5	R-1	5" x 8 1/4"	25'-9 1/4"	24F-V3	Glu-Lam, Stained "Natural"
12,677 Fbm	Deck	4		2" x 8"	94/10' 423/16' 100/18'	#1	SYP, CM-EV21S, KD, Stained "Natural"
560 Fbm	Fascia	4		2" x 10"	4/12' 8/14' 11/16'	#1	SYP, CCA 0.4 pcf, Stained "Natural"
24 Fbm	Cap Plate	2		2" x 6"	2/12'	#1	SYP, CCA 0.4 pcf, Stained "Natural"
96 Fbm	Duct Framing	4		2" x 6"	6/16'	#1	SYP, Stained "Natural"
69 Fbm	Nailer	4		2" x 4"	4/12' 4/14'	#1	SYP, Stained "Natural"
48 Fbm	Box Header	2		2" x 8"	2/8' 2/10'		YZK
1,024 Fbm	Studs & Tp Plate	2		2" x 6"	8/12' 58/16"		YZK
284 Fbm	Bottom Plate	2		2" x 6"	6/10' 14/16'		YZK, Treated CCA 0.4 pcf
107 Fbm	Privacy Studs	2		2" x 4"	10/8' 8/10'		YZK, Treated CCA 0.4 pcf
37 Bags.	Batt Insulation	2	R-19				Walls: K1250 R19 15" x 93" Faced
177 Pcs.	Rigid Insulation	2			4' x 8'		Roof
2 Pcs.	OSB	2		1/2"	4' x 8'		OSB Sheathing for Built-up Columns
250 Pcs.	OSB	2		7/16"	4' x 8'		OSB Sheathing for Ext. Siding & Roof
6 Rolls	15# Asphalt Felt	2					Between siding & sheathing
3,270 Fbm	Siding	2					Cedar Lap Siding
160 Fbm	Trim	2		1" x 4"	42/10' 5/12'		Cedar Trim
61 Pcs.	Dry Wall	1		5/8"	4' x 8'		UL Classification Marking
58 Pcs.	Dry Wall	2		1/2"	4' x 8'		Moisture Resistant
73 Pcs.	FRP Panles	2			4' x 8'		FRP Panels - Beige
7 Can	Adhesive	2		5 Gallon			Field Laminate to dry wall
21 Pcs.	Inside Corner	2			8'		For FRP Panels - Beige
57 Pcs.	Cap Trim	2			8'		For FRP Panels - Beige
68 Pcs.	Division Trim	2			8'		For FRP Panels - Beige
6 Pcs.	Exterior Doors	2		3'-0" x 6'-8"	18ga.door 16ga.frame		Prime painted Steel w/ Hardware
1 Pcs.	Roll-up Window	2		8'-0" x 4'-0"			

Hardware				Steel Connections				
Item	Size	Qty	Remarks	Item	Qty	Pg	MK	Remarks
Hex Nut	3/4"	4	S-2	Plate	16	5	MK-1	S-1
T-Rod	3/4" x 26"	2	S-2	Simpson Joist Hanger	30	4		2x6
Washer	3/4"	4	S-2	Simpson HDU2-SDS2.5	22 Pcs.	3	S-4	w/ SDS Screws, Galv.
A.R. Nails	4 gauge x 2 1/2"	456 Pcs.	S-1, Galv.	Simpson SDS Screws	143	3	S-4	1/4 x 2, Galv.
Screws	2 1/2"	10 #	drywall					

50' x 100' Laminated Beam Gable Pavilion with Restrooms & Concession Community Park Boiling Springs, PA RCP Project No. 08-289	RCP Shelters, Inc. 2100 SE Rays Way * Stuart, FL 34994 Ph: (800) 525-0207 * Fax: (772) 288-0207 E-Mail: info@rcpshelters.co 6/15/2009
---	---

Bill of Materials - RCP # 08-289

Plumbing Fixtures - May deliver separately.		
Item	Qty	Remarks
Handicap Water Closet	2 Pcs.	Toto CT705L w/ seat & TMT1NNC-32 Flush Valve
Standard Water Closet	2 Pcs.	Toto CT705 w/ seat & TMT1NNC-32 Flush Valve
Urinal	2 Pcs.	Toto UT447 & TMU1NNC-12 Flush Valve
Lavatory	6 Pcs.	Toto LT307.4 w/ JB Allen Grid Drain 1042L
Dual Temp Auto Closing Faucet	6 Pcs.	Moen - 8886
Stainless Steel Mirror	6 Pcs.	16" x 36" Polished SS
Toilet Paper Dispenser	4 Pcs.	2 Roll, Stainless Steel
36' Grab Bars	2 Pcs.	American Accessories -GA3-SFX36
42' Grab Bars	2 Pcs.	American Accessories -GA3-SFX42
18' Grab Bars	2 Pcs.	American Accessories -GA3-SFX18
Partitions	2 Lot.	Comtec "Color TBD"

Electric Fixtures - May deliver separately.		
Flourescent Light Fixture	26 Pcs.	LITHONIA - DMW232MVOLTGEB10IS (bulbs not included)
20 AMP Single Pole Breakers	26 Pcs.	GE - Q Line Series
20 AMP Double Pole Breakers	4 Pcs.	GE - Q Line Series
230 AMP Double Pole Breakers	5 Pcs.	GE - Q Line Series
200 AMP Load Center	1 Pcs.	GE - Power Mark Gold Series
400 AMP Load Center	1 Pcs.	GE - Power Mark Gold Series
GFCI Outlets	25 Pcs.	Leviton - 7599-1
Light switches	8 Pcs.	Leviton - CS115-2I

50' x 100' Laminated Beam Gable Pavilion with Restrooms & Concession Community Park Boiling Springs, PA RCP Project No: 08-289	Page 2.	RCP Shelters, Inc. 2100 SE Rays Way * Stuart, FL 34994 Ph: (800) 525-0207 * Fax: (772) 288-0207 E-Mail: info@rcpshelters.co	6/15/2009
---	---------	--	-----------